



## RESIDENTIAL CONSTRUCTION HEAT GUIDELINES

The following guidelines for construction heat have been developed from current local codes. Questions regarding these guidelines should be directed to the Citizens Gas Marketing Department at 927-4328 or the Gas Operation Services Superintendent at 927-6018.

### I. PROCESS FOR CONSTRUCTION HEAT

1. Specify construction heat when you request new service on a home.
2. The meter will be set prior to having any appliances installed.
3. The yard must be within 6 inches of final grade.
4. The houseline piping must be permanent to qualify.
5. Once the service line is installed, call 317-927-4328 for a meter set.

### II. GUIDELINES FOR CONSTRUCTION HEAT

1. Gas hose, if used, must be protected from damage and AGA certified for use with natural gas, or approved for use with natural gas by the State Fire Marshall.
2. The connection at the appliance must be made as follows: valve, nipple, union, and appliance.
3. Temporary construction heaters must be listed or approved as such by a recognized agency.
4. All rigid piping systems must be in accordance with all applicable State and Local codes and follow acceptable pipe installation practices.
5. Any regulator used for construction heat shall be vented to open atmosphere if not designed by the manufacturer to be used with an approved leak limiting device. Flexible hose used for venting of regulators shall be AGA approved.
6. Builder is required to have a licensed contractor test any new houselines and all appliances that are installed.

*The undersigned has agreed to follow Citizens Gas' guidelines for construction heat as listed above. Responsibility to these guidelines will be enforceable as long as temporary heat is used.*

NAME: \_\_\_\_\_

COMPANY: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

CITY: \_\_\_\_\_

STATE: \_\_\_\_\_

ZIP: \_\_\_\_\_

SERVICE ADDRESS: \_\_\_\_\_

PHONE: \_\_\_\_\_

DATE: \_\_\_\_\_

11/6/07